

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20547-00-01

Spot: S2S2NENW

Sec/Twnshp/Rge: 29-28S-32W

4030 feet from S Section Line, 3300 feet from E Section Line

Lease Name: GREEN COURT FARMS

Well #: A1

County: HASKELL

Total Vertical Depth: 5757 feet

Operator License No.: 4549

CIBP Size: feet: 4100 WITH 2 SX CMT

Op Name: ANADARKO PETROLEUM CORPORATI

PROD Size: 5.5 feet: 5338 WITH 460 SX CMT

Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380

SURF Size: 8.625 feet: 1792 WITH 875 SX CMT

\$187¹⁰

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 07/15/2004 1:00 PM

Plug Co. License No.: 31151

Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON

Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 4100' WITH 2 SX CMT. PLUG AT 1820' WITH 50 SX CMT. PLUG AT 600' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON

WitnessType: NONE

Date/Time Plugging Completed: 07/16/2004 11:00 AM

KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 5264'. SET CIBP @ 4100' WITH 2 SX CMT ON TOP. 1ST PLUG PULL OUT OF HOLE TO 1820'. CIRCULATE HOLE & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 800'. LOAD HOLE & PUMP 30 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

RECEIVED
JUL 23 2004
KCC WICHITA


Perfs:

Top	Bot	Thru	Comments
4163	5216		

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2420' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland
JIM HOLLAND
(TECHNICIAN)

INVOICED
DATE 7-23-04
INV. NO. 2005060175

[Signature]
Form C-2/3