

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21030-00-00
Spot: NESWSWSW Sec/Twnshp/Rge: 3-31S-40W
554 feet from S Section Line, 4726 feet from E Section Line
Lease Name: WILLIAMS Well #: L 1
County: MORTON Total Vertical Depth: 5807 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380

CIBP Size: feet: 5000 WITH 2 SX CMT
MSCC Size: feet: 2593 WITH 75 SX CMT
PROD Size: 5.5 feet: 5200 WITH 295 SX CMT
SURF Size: 8.625 feet: 1647 WITH 775 SX CMT

\$188¹³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/08/2004 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Revd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 5000' & 2 SX CMT. PLUG AT 1670' WITH 50 SX CMT. PLUG AT 550' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/08/2004 4:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 5146'. CIBP @ 5000' & SPOT 2 SX CMT ON TOP. 1ST PLUG PULL OUT OF HOLE TO 1670'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 550'. LOAD HOLE & PUMP 30 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5048	5068		

RECEIVED
JUL 23 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1944' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
JUL 14 2004
KCC Dodge City

Signed

Jim Holland
(TECHNICIAN)

INVOICED
DATE 7.23-04
INV. NO. 2005060175

[Signature]