

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22806-00-00  
Spot: S2N2N2NE Sec/Twnshp/Rge: 31-33S-13W  
460 feet from N Section Line, 1370 feet from E Section Line  
Lease Name: RICKE F Well #: 2  
County: BARBER Total Vertical Depth: 5360 feet

Operator License No.: 33168  
Op Name: WOOLSEY OPERATING COMPANY, LL  
Address: 125 N. MARKET, SUITE 1000  
WICHITA, KS 67202

CIBP Size: feet: 2840 WITH 2 SX CMT  
PROD Size: 4.5 feet: 2948 WITH 100 SX CMT  
SURF Size: 10.75 feet: 231 WITH 200 SX CMT

*\$174<sup>20</sup>*

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/20/2004 12:15 PM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: JOHN SWINFORD Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET 4-1/2" CIBP @ 2840' W/2 SX CEMENT ON TOP. CUT CASING @ FREEPOINT. SPOT 40 SX PLUG @ 600', 40 SX @ 250' AND 10 SX @ 40' TO SURFACE. 60/40 6% GEL.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/20/2004 1:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 2893'. SET CIBP @ 2840' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID DOWN 4 1/2" CASING & RUN 2 3/8" TUBING IN TO PLUG THROUGH. 1ST PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 250' WITH 65 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2864	2868		

RECEIVED  
JUL 23 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2400' OF 4 1/2" CASING.

Plugged through: TBG

District: 01

RECEIVED  
JUL 21 2004  
KCC Dodge City

Signed

*Stephen J. Smith*  
(TECHNICIAN)

INVOICED

DATE 7.23.04  
INV. NO. 2005060181

Foam CP-1/3