



15-023-20004-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 21 1968
 CONSERVATION DIVISION
 Wichita, Kansas
 10-21-68

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Al. Thompson of Mack Oil Company, has this date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company,

Complete Address: 812 Union Center Building, Wichita, Kansas.

Lease Name: Cook Well No. 1

Location: CSE-SE Sec. 9 Twp. 2 Rge. (E)(W) 40

County: Cheyenne Total Depth 5280 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Thompson was instructed to plug the well as follows:

356'--8 5/8" Surface casing, cement circulated with 350 Sx.
Top of Dakota section @ 2400'.

Circulate hole with heavy mud. Pull DP to 2650' and displace 100 Sx.
cement thru DP. Pull DP to 380' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. A. Nichols
 Conservation Division Agent