



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 14 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 7-14-69

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. John Scarbrough of Thomas Drilling Company, Inc. has this date requested permission to plug the following described well:

Mr. Scarbrough guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company,

Complete Address: 812 Union Center Building, Wichita, Kansas.

Lease Name: Edie Well No. 1

Location: CNE-SW Sec. 16 Twp. 2 Rge. (E)(W) 37

County: Cheyenne Total Depth 5128' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Scarbrough was instructed to plug the well as follows:

385'--8 5/8" Surface casing, cement circulated with 250 Sx.  
Top of Dakota section @ 2138'.

Circulate hole with heavy mud. Pull DP to 2500' and displace 120 Sx.  
cement thru DP. Pull DP to 400' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

M. G. Nichols  
 Conservation Division Agent