



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

15-153-20132-00-00

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
01-06-1972  
JAN 6 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. R. L. Sixbury of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Sixbury guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company.

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name: Bliss Well No. 1

Location: NW-SW Sec. 33 Twp. 2 Rge. (E)(W) 34

County: Rawlins Total Depth 4010' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Sixbury was instructed to plug the well as follows:

247'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1750'.

Circulate hole with heavy mud. Pull DP to 1975' and displace 110 Cu. Ft. cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent