



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-153-20146-00-00

RECEIVED  
STATE CORPORATION COMMISSION

FEB 26 1973  
02-26-1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. R. L. Sixbury of Murfin Drilling Company has this

date requested permission to plug the following described well:

Mr. Sixbury guarantees payment of the plugging fee.

Operator's full Name: Basin Petroleum Corporation,

Complete Address: 900 Fidelity Plaza, Oklahoma City, Oklahoma

Lease Name: Ankle Well No. 1

Location: NW-NW-NE Sec. 32 Twp. 2 Rge. (E)(W) 34

County: Rawlins Total Depth 4230' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Sixbury was instructed to plug the well as follows:

30 1/2' -- 8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1750'.

Circulate hole with heavy mud. Pull DP to 1975' and displace 110 Cu. Ft. cement thru DP. Pull DP to 310' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent