

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 7 1967
12-07-1967
CONSERVATION DIVISION
Wichita, Kansas

15-153-20014-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dale Bucheister of John O. Farmer, Incorporated has this date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: Brooks Hall,

Complete Address: 1704 Liberty Bank Building, Oklahoma City, Oklahoma.

Lease Name: Prohazka Well No. 1

Location: CNE-SW Sec. 32 Twp. 2 Rge. (E)(W) 34

County Rawlins Total Depth 4295 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bucheister was instructed to plug the well as follows:

201'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Dakota section from 2050' to 2250'.

Circulate hole with heavy mud. Pull DP to 2275' and displace 100 Sx. cement thru DP. Pull DP to 210' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent