



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

15-153-20164-00-00

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 24 1973  
08-24-1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. R. L. Sixbury of Murfin Drilling Company has this  
date requested permission to plug the following described well:

Mr. Sixbury guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 Fourth National Bank Building, Wichita, Kans.

Lease Name: Franklin Well No. 1

Location: App:-SW-SW-NE Sec. 9 Twp. 2 Rge. (E)(W) 3/4

County: Rawlins Total Depth 4114' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sixbury was instructed to plug the well as follows:

297'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1875'.

Circulate hole with heavy mud. Pull DP to 2100' and displace 110 Cu. Ft.  
cement thru DP. Pull DP to 310' and displace 30 Cu. Ft. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to  
bottom of cellar.

Very truly yours,

*W. L. Nichols*  
Conservation Division Agent