



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-153-20047-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. John Scarbrough of Thomas Drlg. Co., Inc. has this
date requested permission to plug the following described well:

Mr. Scarbrough guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company,

Complete Address: McCasland Building, Duncan, Oklahoma.

Lease Name: Haller Well No. 1

Location: CNW-SW Sec. 7 Twp. 2 Rge. (E)(W) 34

County: Rawlins Total Depth 1750' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Scarbrough was instructed to plug the well as follows:

361'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota 1550' to 1880'.

Circulate hole with heavy mud. Pull DP to 1775' and displace 100 Sx.
cement thru DP. Pull DP to 400' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

RECEIVED
STATE CORPORATION COMMISSION
07-23-1969
JUL 23 1969

CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

M. L. Dickel
Conservation Division Agent