



ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Al Thompson of Mack Oil Company, has this date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company,

Complete Address: 812 Union Center Building, Wichita, Kansas.

Lease Name: Raile Well No. 1

Location: CSE-SE Sec. 25 Twp. 2 Rge. (E)(W) 41

County: Cheyenne Total Depth 5300 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Thompson was instructed to plug the well as follows:

361'--8 5/8 Surface casing, cement circulated with 350 Sx.  
Top of Dakota section @ 2465.

Circulate hole with heavy mud. Pull DP to 2690' and displace 100 Sx.  
cement thru DP. Pull DP to 370' and displace 30 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 7 - 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
16-7-68

Very truly yours,

M. S. Nichols  
Conservation Division Agent