

KANSAS

AL

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-023-20004-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1968
CONSERVATION DIVISION
Wichita, Kansas
10-21-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mack Oil Company,

Complete Address: 812 Union Center Building, Wichita, Kansas.

Lease Name Cook Well No. 1

Location GSE-SE Sec. 9 Twp. 2 Rge. (E) (W) 40

County Cheyenne Total Depth 5280

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 7:30 PM Day 16 Month 10 Year 1968

The Above well was plugged as follows:

356'--8 5/8" Surface casing, cement circulated with 350 Sx.
Top of Dakota section @ 2400'.

Circulated hole with heavy mud. Pulled DP to 2650' and displaced 100 Sx. cement thru
DP from 2650' to 2325'. Pulled DP to 380' and displaced 20 Sx. cement thru DP from
380' to 320'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Dehals*
Well Plugging Supervisor

DATE 10/21/68
INV. NO. 8604-W