

P KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-023-30024-00-00

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAY 26 1965
5-26-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated,

Complete Address: 370 West Wichita, Russell, Kansas.

Lease Name Kehlbeck Well No. 1

Location CSE-NE Sec. 20 Twp. 2 Rge. (E) (W) 37

County Cheyenne Total Depth 5100

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 6:00PM Day 22 Month 5 Year 1965

The Above well was plugged as follows:

263'--8 5/8" Surface pipe, cement circulated with 150 Sx.

Circulated hole with heavy mud, set plug @ 660' and displaced 20 Sx. cement

thru DP. Heavy mud to 250', set plug with 1/4 sack hulls and displaced 20 Sx.

cement thru DP. Heavy mud to 40', set plug with 1/2 sack hulls and 10 sacks

cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *H. L. Nichols*
Well Plugging Supervisor

DATE 5/26/65

INV. NO. 1214-W