

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-023-20006-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1969
CONSERVATION DIVISION
Wichita, Kansas
7-14-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mack Oil Company,

Complete Address 812 Union Center Building, Wichita, Kansas.

Lease Name Edie Well No. 1

Location CNE-SW Sec. 16 Twp. 2 Rge. (E) (W) 37

County Cheyenne Total Depth 5128'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Thomas Drilling Company, Incorporated,

Address Box #100, Duncan, Oklahoma. License No. _____

Operation Completed: Hour 7:30 PM Day 8 Month 7 Year 1969

The above well was plugged as follows:

385'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 2138'.

Circulated hole with heavy mud. Pulled DP to 2195' and displaced 120 Sx. cement thru
DP from 2195' to 2100'. Pulled DP to 1400' and displaced 20 Sx. cement thru DP from
1400' to 340'. Pulled DP, set bridge @ 140' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 7/14/69

INV. NO. 99-11