

RECEIVED
STATE CORPORATION COMMISSION

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
CONSERVATION DIVISION AGENT'S REPORT

JUL 28 1961 7-28-61

15-023-00016-00-00

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Cheyenne
Location: 2687' from E line
3897' " S " SESE NW Sec. 16 Twp. 25 Rge. _____ (E) _____ (W) 37
Name of Field: _____ Total Depth: 4960

I have this date completed supervision of plugging of:

Lease Name: Wilkinson WICKENS Well No. 1

Operator's Full Name: Phillips Pet Co

Complete Address: Box 779 Great Bend, Kansas

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kansas License No. 436

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes No

If yes how long? _____ Reason: _____

Operation Completed: Hour 8PM Day 18 Month 7 Year 61

The above well was plugged as follows:

8 5/8" 365' circulated with cement. 4 1/2" 4951' with 85 sax cement - perf
4230' - PB to 4270 - filled with sand to 4200', set 5 sax cement with dump
bailer - pulled 4 1/2" - filled hole with heavy rotary mud to 365', set bridge
and 25 sax cement, heavy mud to 35', set bridge and 10 sax cement to bottom
cellar.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 8/7/61
INV. NO. 3508-W