

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

15-023-30013-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 28 1964  
10-28-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Amax Petroleum Corporation,

Complete Address: 507 Enterprose Building, Tulsa, Oklahoma.

Lease Name Wilkins Well No. 1

Location CNE-NW Sec. 10 Twp. 2 Rge. (E) (W) 37

County Cheyenne Total Depth 5100

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Murfin Drilling Company,

Address: 617 Union Center, Wichita, Kansas. License No.     

Operation Completed: Hour 8:30AM Day 24 Month 10 Year 1964

The Above well, was plugged as follows:

291'--8 5/8" Surface pipe, cement circulated with 200 Sx.  
Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.  
cement thru DP. Heavy mud to 280', set plug with 1/2 sack hulls and dis-  
placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack  
hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: V. L. Deibel  
Well Plugging Supervisor

DATE 10/28/64  
INV. NO. 64-W