

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

Form CP-3
6-26-62
RECEIVED
STATE CORPORATION COMMISSION
NOV 7 1968
CONSERVATION DIVISION
Wichita, Kansas
11-7-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-023-2000500-00

Operator's Full Name Mack Oil Company,
Complete Address: 812 Union Center Building, Wichita, Kansas.
Lease Name Wilkens Well No. 1
Location App.-CS/2-SE-SE Sec. 8 Twp. 2 Rge. (E) (W) 37
County Cheyenne Total Depth 5035'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Above
Address: License No.
Operation Completed: Hour 1:00 PM Day 5 Month 11 Year 1968

The Above well was plugged as follows:

332'--8 5/8" Surface casing, cement circulated with 300 Sx.
Top of Dakota section @ 2225'.

Circulated hole with heavy mud. Pulled DP to 2500' and displaced 115 Sx. cement
thru DP from 2500' to 2125'. Pulled DP to 360' and displaced 25 Sx. cement thru DP
from 360' to 285'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICE
DATE 11/9/68
INV. NO. 8983-11

Signed: M. L. Dehols
Well Plugging Supervisor