

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-153-20132-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 6 1972
01-06-1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Murfin Drilling Company,
Complete Address 617 Union Center Building, Wichita, Kansas.
Lease Name Bliss Well No. 1
Location NW-SW Sec. 33 Twp. 2 Rge. (E) (W) 34
County Rawlins Total Depth 4010'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above

Address License No.
Operation Completed: Hour 5:00 AM Day 2 Month 1 Year 1972

The above well was plugged as follows:

247'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1750'.

Circulated hble with heavy mud. Pulled DP to 1975' and displaced 110 Cu. Ft. cement
thru DP from 1975' to 1650'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 1-11-72

INV. NO. 4933-W