

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1973
08-24-1973
CONSERVATION DIVISION
Wichita, Kansas

15-153-20164-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Empire Drilling Company.

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Franklin Well No. 1

Location App:-SW-SW-NE Sec. 9 Twp. 2 Rge. (E) (W) 34

County Rawlins Total Depth 4111'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kans. License No.

Operation Completed: Hour 2:30 PM Day 22 Month 8 Year 1973

The above well was plugged as follows:

297'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1875'.

Circulated hole with heavy mud. Pulled DP to 2100' and displaced 110 Cu. Ft. cement
thru DP from 2100' to 1775'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 8/24/73
INV. NO. 7818-112

Signed: M. L. Nichols
Well Plugging Supervisor