

14

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-153-20047-00-00

Operator's Full Name Mack Oil Company,

Complete Address McCasland Building, Duncan, Oklahoma.

Lease Name Haller Well No. 1

Location CNW-SW Sec. 7 Twp. 2 Rge. (E) (W) 34

County Rawlins Total Depth 4750'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Thomas Drilling Company, Incorporated,

Address Box #400, Duncan, Oklahoma. License No. _____

Operation Completed: Hour 1:45 AM Day 21 Month 7 Year 1969

The above well was plugged as follows:

361'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1550'.

Circulated hole with heavy mud. Pulled DP to 1775' and displaced 100 Sx. cement thru
DP from 1775' to 1450'. Pulled DP to 400' and displaced 20 Sx. cement thru DP from
400' to 340'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

RECEIVED

STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED

CONSERVATION DIVISION

Wichita, Kansas

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 7/23/69

INV. NO. 143-11

JUL 23 1969
07-23-1969