

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-153-20146-00-00

FEB 26 1973
02-261973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Basin Petroleum Corporation,
Complete Address 900 Fidelity Plaza, Oklahoma City, Oklahoma.
Lease Name Ankle Well No. 1
Location NW-NW-NE Sec. 32 Twp. 2 Rge. (E) (W) 34
County Rawlins Total Depth 4230'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Murfin Drilling Company,
Address 617 Union Center, Wichita, Kansas License No.
Operation Completed: Hour 12:30 AM Day 8 Month 2 Year 1973

The above well was plugged as follows:

304'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1750'.

Circulated hole with heavy mud. Pulled DP to 1975' and displaced 110 Cu. Ft. cement
thru DP from 1975' to 1650'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed:

W. L. Nichols
Well Plugging Supervisor

DATE 2/28/73

INV. NO. 7048-W