

Y
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-153-20017-00-00

RECEIVED
STATE CORPORATION COMMISSION
04-19-1968
APR 19 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name J. M. Stewart,

Complete Address: 608 Union Center Building, Wichita, Kansas.

Lease Name Ankle Estate Well No. 1

Location NW-NE-NE Sec. 32 Twp. 2 Rge. (E) (W) 34

County Rawlins Total Depth 4565

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Incorporated,

Address: Box # 486, Great B end, Kansas. License No.

Operation Completed: Hour 4:30 PM Day 14 Month 4 Year 1968

The Above well was plugged as follows:

248'--8 5/8" Surface pipe, cement circulated with 180 Sx.
Top of Dakota section @ 1700'.

Circulated hole with heavy mud. Pulled DP to 1925' and displaced 100 Sx. cement thru
DP from 1925' to 1600'. Pulled DP to 270' and displaced 20 Sx. cement thru DP from
270' to 210'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/19/68
INV. NO. 7604-W

Signed: [Signature]
Well Plugging Supervisor