

KANSAS

*Y*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-153-20014-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 7 1967  
12-07-1967  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Brooks Hall,

Complete Address 1704 Liberty Bank Building, Oklahoma City, Oklahoma.

Lease Name Prohazka Prochazka Well No. 1

Location CNE-SW Sec. 32 Twp. 2 Rge. (E) (W) 34

County Rawlins Total Depth 4295'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor John O. Farmer, Incorporated,

Address 370 W. Wichita, Russell, Kansas. License No.     

Operation Completed: Hour 4:15 AM Day 2 Month 12 Year 1967

The above well was plugged as follows:

201'--8 5/8" Surface pipe, cement circulated with 150 Sx.  
Dakota section from 2050' to 2250'.

Circulated hole with heavy mud. Pulled DP to 2275' and displaced 100 Sx. cement thru  
DP from 2275' to 2050'. Pulled DP to 210' and displaced 20 Sx. cement thru DP from  
210' to 160'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. R. Nichols  
Well Plugging Supervisor

DATE 12/7/67  
INV. NO. 6855-W