

P

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 023 - 20,090 - 00-00 (of this well)

Operator's Full Name J-W Operating Co.

Complete Address 1900 LTV Tower, Dallas, Texas

Lease Name Isaac Sampler Unit Well No. 1

Location 1000' FEL & 1550' FSL Opp. C 1/2 SW NE SE Sec. 4 Twp. 2 Rge. (E) (W) 42

County Cheyenne Total Depth 2191'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Excell Drlg. by Cementing, Inc. Scotsbluf, Neb.

Address Raye, Colorado License No.

Operation Completed: Hour 8 A Day 16 Month 12 Year 1978

The above well was plugged as follows:

RTD 2191' 7" csg set 210' cwc Plg. Mat. 50-50 poz 2% total gel. 6 1/4" hole.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 2190' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

DEC 19 1978 12-19-78

I hereby certify that the above well was plugged as herein stated.
Wichita, Kansas

INVOICED

Signed: Reo Massey
Well Plugging Supervisor

DATE 12.26.78
INV. NO. 8786-W