

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

15-153-30123-00-00  
WELL PLUGGING RECORD

Rawlins County. Sec. 30 Twp. 2S Rge. 34 (W) (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines G-SW-SE  
Lease Owner Amerada Petroleum Corporation  
Lease Name Walter Cooper Well No. 1  
Office Address Box 197, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed 8-30- 1960  
Application for plugging filed 8-30- 1960  
Application for plugging approved 8-30- 1960  
Plugging commenced 8-30- 1960  
Plugging completed 8-30- 1960  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19 -  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A.D. Fabricius, Hill City, Kansas  
Producing formation - Depth to top - Bottom - Total Depth of Well 4667 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	348'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Halliburton Spotted Cement Plug Thru 4 $\frac{1}{2}$ " Drill Pipe As Follows:

500' to 440' W/20 Sacks Cement  
345' to 285' W/20 Sacks Cement  
30' to Top W/10 Sacks Cement

Plugging Supervised by Mr. A.D. Fabricius, State Plugger, Hill City, Kansas.  
Started Plugging at 2:00 p.m. 8-30-60, Finished at 5:30 p.m. 8-30-60

RECEIVED  
STATE CORPORATION COMMISSION  
09-02-1960  
SEP 2 1960

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Jelly Reaves Drilling Company  
Address P.O. Box 1264, Cushing, Oklahoma

STATE OF Kansas, COUNTY OF Barton, ss.  
Ernest Higgins (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Higgins  
Ernest Higgins-Foreman

(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of August 19 60

Charles W. Anderson  
Notary Public.

My commission expires November 21, 1961



15-153-30123-00-00

D R I L L E R ' S L O G

WELL: Walter Cooper No. 1 - C-SW/4-SE/4, Section 30:2S-34W,  
Rawlins County, Kansas  
Amerada Petroleum Corporation

8-5/8" OD Casing Cemented at 348'

Drilling Commenced 8-15-60  
Drilling Completed 8-29-60

FROM	TO	FORMATION	
0'	80'	Shale	
80'	120'	Sand	
120'	200'	Shale	
200'	220'	Sand	
220'	2085'	Shale	
2085'	2464'	Sand	
2464'	2474'	Anhydrite	
2474'	2582'	Shale	
2582'	2590'	Anhydrite	
2590'	2860'	Shale	
2860'	2900'	Sand	
2900'	3054'	Shale	
3054'	3091'	Sand	
3091'	3115'	Shale	
3115'	3130'	Sand	
3130'	3148'	Shale	
3148'	3210'	Red Bed	
3210'	3525'	Shale	
3525'	3570'	Lime	
3570'	3590'	Sand	
3590'	3655'	Shale	
3655'	3800'	Lime	
3800'	3830'	Shale	
3830'	3900'	Lime	
3900'	3950'	Shale	
3950'	3975'	Sand	
3975'	4498'	Lime	
4498'	4502'	Sand	
4502'	4523'	Lime	
4523'	4553'	Broken Sand	
4553'	4595'	Shale	
4595'	4667'	Lime	
	4667'	Total Depth	Dry and Abandoned

"8-5/8" OD 2 1/4" Casing Cemented with 300 Sacks Common Cement W/ 2% Calcium Chloride at 348'."

RECEIVED  
STATE COMMISSION  
SEP 2 1960  
CONSERVATION DIVISION  
Wichita, Kansas