

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-153-20816-00-00

LEASE NAME Domsch Bros.

WELL NUMBER #1

3630 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 27 TWP. 2S RGE. 34W (E) or (W)

COUNTY Rawlins

Date Well Completed 2-12-98

Plugging Commenced 2-12-98

Plugging Completed 2-12-98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Thoroughbred Associates, LLC

ADDRESS 10 Colonial Court, Wichita KS 67207

PHONE# (316) 685-1512 OPERATORS LICENSE NO. 31514

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 12, 1998 (date)

by Ed Schumacher, KCC Hays (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4275'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		275	surf	8-5/8"	275'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Plug with 190 sxs 60/40 pozmix, 6% gel. 1st plug set at 2850' w/25 sxs; 2nd plug set at 2155' w/100 sxs; 3rd plug set at 325' w/40 sxs; 4th plug set at 40' w/10 sxs; and 15 sxs in rathole.

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____

Address _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Thoroughbred Associates, LLC

STATE OF Kansas COUNTY OF Sedgwick, ss.

Robert C. Patton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Robert Patton

(Address) 10 Colonial Ct. Wichita KS 67207

SUBSCRIBED AND SWORN TO before me this 23rd day of April, 19 98

Karri Wolken Notary Public

