

15-153-00057-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

RAWLINS

County. Sec. 16 Twp. 2S Rge. 34W (E) (W)

Location as "NE/CNW%SW%" or footage from lines NW NW SE

Lease Owner K & E & BRADLWY BROS.

Lease Name FOCKE Well No. 1

Office Address 719 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed August 22nd, 1959 19

Application for plugging filed August 22nd, 1959 19

Application for plugging approved August 22nd, 1959 19


Plugging commenced August 22nd, 1959 19

Plugging completed August 22nd, 1959 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 5091' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	425'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 600' set plug with 20 sx cement through drill pipe. Filled with heavy mud to 420' set plug with 10 sx cement through drill pipe. Filled with heavy mud to 40' set plug with 10 sx cement to base of cellar. Job complete 8-22-59.

RECEIVED
STATE CORPORATION COMMISSION
09-02-1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor K & E DRILLING, INC.
Address 719 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Clinton Engstrand (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clinton Engstrand, K & E DRILLING, INC.
719 Union Center, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 31st day of August, 1959.

My commission expires August 11th, 1962. Patricia M. Edwards, Notary Public.

PLUGGING
FILE SEC 16 T 2 R 34W
BOOK PAGE 1 LINE 29

15-153-00057-00-00
DRILLER'S WELL LOG

OPERATOR: **K & E & BRADLEY BROS.**
 719 Union Center
 Wichita, Kansas

WELL NAME: **#1 FOCKE**
 LOCATION: **NW NW SE**
Sec. 16-28-34W
RAWLINS CO, KANSAS

CONTRACTOR: **K & E DRILLING, INC.**
 719 UNION CENTER BLDG.
 WICHITA, KANSAS

COMMENCED: **August 9th, 1959**

CASING RECORD: **8-5/8" @ 425' (300 sz cnt)**

COMPLETED: **August 22nd, 1959**

ELEVATION: **3136' KB**

ROTARY TOTAL DEPTH: **5091'**

PRODUCTION: **D & A**

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Shale	108
Sand	123
Shale	1915
Sand & Shale	2180
Shale	2200
Shale & Shells	2315
Sand (hard)	2345
Shale, Sand & Lime	2420
Sand & Shale	2500
Lime & shale	2650
Shale	2746
Anhydrite	2770
Shale	2935
Anhydrite	2960
Lime & Shale	3805
Lime	4460
Sand, Shale & Lime	4560
Sand & Shale	4695
Chert	4700
Chert & lime	4750
Lime	5055
Sand	5069
Granite	5091
R.T.D.	5091

FILED
 STATE COMMISSION
 SEP 2 1959
 CONSERVATION DIVISION
 Wichita, Kansas

CERTIFICATION

State of KANSAS }
 County of SEDGWICK } ss:

I, Clinton Engstrand, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Subscribed and sworn to before me this 31st day of August, 1959

Clinton Engstrand
 Clinton Engstrand

My Commission expires: August 11th, 1962. Patricia M. Edwards, Notary Public.

PLUGGING
 FILE SEC. 16 T 2 R 34W
 BOOK PAGE 1 LINE 29

