


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

CHEYENNE County. Sec. 34 Twp. 2S Rge. (E) 42 (W)
Location as "NE/CNW/SW" or footage from lines. Ctr SE/4 of SE/4
Lease Owner E. J. ATHENS
Lease Name ZWEYGARDT Well No. 1
Office Address PHILTOWER BLDG TULSA 3, OKLAHOMA
Character of Well (completed as Oil, Gas or Dry Hole) DRY
Date well completed 1-1 19 60
Application for plugging filed 1-1 (Phone) 19 60
Application for plugging approved 1-1 (Phone) 19 60
Plugging commenced 1-2 19 60
Plugging completed 1-2 19 60
Reason for abandonment of well or producing formation No commercial shows in well
If a producing well is abandoned, date of last production ----- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricus
Producing formation ---- Depth to top ---- Bottom -- Total Depth of Well 5445 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand	Fresh Water	175	210	8 5/8	268	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled to top with heavy rotary mud and spotted cement plugs (regular cement) as follows:
20 sacks plug at 600'
20 sacks plug at 300'
10 sacks plug at 308 to surface

Plugging schedule authorized by plugging agent

REC'D
STATE CORP. COM.
JAN 15 1960
CONSERVATION DIVISION
Wichita, Kansas

1-6-60

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor REED DRILLING COMPANY, INC.
Address 1209 Atlas Life Building, Tulsa 3, Oklahoma

STATE OF OKLAHOMA, COUNTY OF TULSA, ss.
R. B. Reed (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) R. B. Reed R. B. Reed
1209 Atlas Life Bldg, Tulsa 3, Okla
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of January, 19 60
Margaret E. Gimes
Notary Public.

My commission expires 12/10/62



15-023-19001-00-00

WELL LOG

WELL: Zwegardt #1
LOCATION: C SE SE 34-2S-42W
Cheyenne County, Kansas

Spudding Date: 12-10-59
Date Casing Set:
Date Rotary Completed: 1-1-60

OWNER: E. J. Athens
Philtower Building
Tulsa 3, Oklahoma

FROM:	TO:	FORMATION:
0	1585	Shale
1585	2175	Shale & Shells
2175	2370	Shale
2370	2395	Lime
2395	2575	Shale
2575	3163	Sand & Shale
3163	3365	Shale & Shells
3365	3665	Shale, Sand, Anhydrite
3665	4060	Shale & Shells
4060	5300	Lime and Shale
5300	5375	Shale
5375	5404	Sand
5404	5455	Lime
5455		

TOTAL DEPTH

RECEIVED
STATE CORPORATION COMMISSION

FEB 12 1960

CONSERVATION DIVISION
Wichita, Kansas

2-12-60

ELECTRIC LOG TOPS:

4590	Lansing
4910	Base Kansas City
5104	Cherokee
5404	Mississippian

I certify the above and foregoing to be a true and exact copy of the original driller's log on the Zwegardt #1.

REED DRILLING COMPANY, INC.

BY: B. B. Reed
PRESIDENT

Subscribed and sworn to before me this 9th day of February, 1960.

Margaret E. Grimes
NOTARY PUBLIC

My Commission Expires December 10, 1962.

Conservation
STATE CORPORATION COMMISSION
FEB 11 1960
Secretary