

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-
API NUMBER 023-20,298-00-00
LEASE NAME Sass 518

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 11-11-1
2310 Ft. from S Section Line
2310 Ft. from E Section Line
SEC. 11 TWP. 2S RGE. 42 (X) or (W)
COUNTY Cheyenne
Date Well Completed 12-18-90
Plugging Commenced 12-18-90
Plugging Completed 12-18-90

LEASE OPERATOR Hillin-Simon Oil Company
ADDRESS P. O. Box 1552, Midland, TX 79702
PHONE# (915) 682-2202 OPERATORS LICENSE NO. 30201
Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-17-90 (date)
by Herb Deinus (KCC District Agent's Name).

Is ACO-1 filed? NO If not, Is well log attached? YES

Producing Formation N/A Depth to Top _____ Bottom T.D. 1779'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Niobrara	water/gas	0'	275'	7"	275'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set Wellbore loaded with mud-laden fluid, mud weight approx. 9.1 ppg, viscosity approx. 55. Mud circulated thru drillpipe at TD. Cmt plug(s) spotted via drillpipe per procedure as required by KCC Dist Office. Cmt slurry consists of 50/50 Pozmix 'A' with 6% gel and 1/4# floccle/sk. Cmt plug spotted from 330' to 3' below ground level inside 7" surface csg. Cutoff 7" csg 3' below ground level.

Name of Plugging Contractor Halliburton Services License No. 5287
Address P. O. Box 1671, Sterling, Colorado 80751

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hillin-Simon Oil Company
STATE OF Texas COUNTY OF Midland, ss. FEB 11 1991
2-11-91

Hillin-Simon Oil Company (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Stan Venable
(Address) P. O. Box 1552, Midland, TX 79702

SUBSCRIBED AND SWORN TO before me this 6th day of February, 19 91



Vicki J. Dillard
Notary Public