

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 023-20,317-00-00

LEASE NAME Northrup 101

WELL NUMBER 20-10-1

1400 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 20 TWP. 2S RGE. 41 ~~xx~~ or (W)

COUNTY Cheyenne

Date Well Completed 11-13-91

Plugging Commenced 11-13-91

Plugging Completed 11-13-91

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Hillin-Simon Oil Company

ADDRESS P. O. Box 1552, Midland, TX 79702

PHONE# (915) 682-2202 OPERATORS LICENSE NO. 30201

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-13-91 (date)

by Herb Deinus (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? YES

Producing Formation N/A Depth to Top \_\_\_\_\_ Bottom T.D. 1738'

Show depth and thickness of all water, oil and gas layers

OIL, GAS OR WATER RECORDS

RECEIVED  
 STATE CORPORATION COMMISSION  
 CASING RECORD  
 2-12-92

Formation	Content	From	Conserved in	Pulled out
Niobrara	water/gas	0	370'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Wellbore loaded with mud-laden fluid, mud weight approx. 9.1 ppg, viscosity approx. 55. Mud circulated thru drillpipe at TD. Cmt plug(s) spotted via drillpipe per procedure as required by KCC Dist Office. Cmt slurry consists of 60/40 Pozmix 'A' with 6% gel and 1/4# floccle/sk. Cmt plug spotted from 430' to 3' below ground level inside 7" surface csg. Cutoff 7" csg 3' below ground level.


Name of Plugging Contractor Halliburton Services License No. 5287  
 Address P. O. Box 1671, Sterling, Colorado 80751

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hillin-Simon Oil Company  
 STATE OF Texas COUNTY OF Midland, ss.

Hillin-Simon Oil Company (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Stan Venable  
 (Address) P. O. Box 1552, Midland, TX

SUBSCRIBED AND SWORN TO before me this 3rd day of February, 1992



Vicki J. Dillard  
 Notary Public