


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-089-00007-00-00 WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Jewell County, Sec. 8 Twp. 3S Rge. 10 (X) W (W)
Location as "NE/CNW/SW" or footage from lines C SE NE
Lease Owner National Drilling Company, Inc. & Irving Nagel
Lease Name Voboril Well No. 1
Office Address 535 Petroleum Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11/28/60 19
Application for plugging filed 11/28/60 19
Application for plugging approved 11/28/60 19
Plugging commenced 11/28/60 19
Plugging completed 11/28/60 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman, Holyrood, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4435 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	197	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole from total depth (4435') to 180' with rotary mud.
Set first plug at 180' with 20 sacks cement. Filled hole from top of first plug to 40 feet with mud. Set second plug at 40 feet with 10 sacks cement. Filled hole to surface with mud.

RECEIVED
STATE CORPORATION COMMISSION
12-07-1960
DEC 7 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor National Drilling Company, Inc.
Address 535 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Howard A. Stoskopf

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Howard A. Stoskopf
535 Petroleum Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of December, 19 60

My commission expires November 14, 1964

Helen Suellentrop
Notary Public.



R

DRILLERS LOG

15-089-00007-00-00 VOBORIL NO. 1

Irving Nagel and

CASING RECORD:
8-5/8" @ 197'
w/150 sx cement

COMPANY: NATIONAL DRILLING CO., INC.
CONTRACTOR: Same

DESCRIPTION: C SE NE
8-3S-10W
Jewell County, Kansas

COMMENCED: 11/15/60
COMPLETED: 11/28/60

ROTARY TOTAL DEPTH: 4435' ELEVATION: 1856 KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Clay	0	50
Shale and Shells	50	200
Shale	200	375
Sand and Shale	375	475
Shale	475	1180
Lime and Shale	1180	1530
Lime with Shale	1530	1570
Lime and Shale	1570	2855
Shale	2855	2885
Lime and Shale	2885	3035
Shale with Lime Stringers	3035	3065
Shale and Shells	3065	3095
Lime	3095	3300
Lime and Shale	3300	3545
Lime and Chert	3545	3607
Lime, Chert and Shale	3607	3650
Shale and Lime w/Chert Streaks	3650	3722
Lime	3722	3795
Lime and Shale	3795	3930
Lime	3930	4064
Shale and Lime	4064	4120
Lime	4120	4290
Lime and Chert	4290	4319
Lime	4319	4435

STATE OF KANSAS
 DEC 7 1960
 CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

NATIONAL DRILLING COMPANY, INC.

Howard A. Stoskopf
 Howard A. Stoskopf

Subscribed and sworn to before me this 6th day of December, 1960.

Helen Suellentrop
 Helen Suellentrop, Notary Public

My commission expires: November 14, 1964.