

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Pratt Well Service, Inc.  
Address: P.O. Box 847, Pratt, KS 67124  
Phone: (620) 672-2531 Operator License #: 5893  
Type of Well: oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: July 9, 2004 <sup>12</sup> KCC BEM 7-29-04 (Date)  
by: \_\_\_\_\_ (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
4344'-46' Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
4336'-38' Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
4320'-23' Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-185-20,756-A00-01  
Lease Name: Shrack  
Well Number: #2 OWWO  
Spot Location (QQQQ): SW KCC BEM 7-29-04 SE - NE/4 - \_\_\_\_\_  
2970' Feet from  North /  South Section Line  
990' Feet from  East /  West Section Line  
Sec. 20 Twp. 25S S. R. 13  East  West  
County: Stafford  
Date Well Completed: July 13, 1985 KCC BEM 7-29-04  
Plugging Commenced: July 7, 2004  
Plugging Completed: July 9, 2004

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	@462'	
				5 1/2"		51 Joints

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Log-Tech set off charge around csg head-pulled 70,000# and slips would not come off. Log-Tech set CIBP @ 4300' and set 2 sks cement on top. Had slips and head cut.  
Loaded csg w/ wtr, shot csg @ 1839', would not move, loggers reloaded and shot csg @ 1621'. It came free. Rigged loggers down and rigged for 5 1/2". Tripped out and laid down 51 Jts-5 1/2". Rigged for tbg, ran 25 Jts-2 7/8" to 800'. Rigged up Acid Services and pumped 15 sks gel and 50 sks 60/40 Poz. Pulled 11 jts and pumped 50 sks of 60/40 Poz and 6% gel; pulled 13 Jts to 32' and pumped remaining cement to surface. 1st plug 800' w/ 50 sks 60/40; 2nd plug 480' w/ 50 sks 60/40; 3rd plug 40' w/ 15 sks 60/40

Name of Plugging Contractor: Pratt Well Service, Inc. License #: 5893  
Address: P.O. Box 847, Pratt, KS 67124  
Name of Party Responsible for Plugging Fees: Pratt Well Service, Inc.  
State of Kansas County, Pratt, ss. \_\_\_\_\_  
Kenneth C. Gates, President (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

RECEIVED  
JUL 28 2004  
KCC WICHITA

(Signature) X Kenneth C. Gates, President  
(Address) P.O. Box 847, Pratt, KS 67124

**AMY S. ROBERTSON**  
Notary Public - State of Kansas  
My Appt. Expires 3/13/08

SUBSCRIBED and SWORN TO before me this 23 day of July, 2004  
Amy Robertson Notary Public My Commission Expires: 3/13/08