

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-113-21293-0000
LEASE NAME Otte A well
WELL NUMBER A#1 6/29/04 7-28-04

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

1250' _____ Ft. from South Line of Section
330' _____ Ft. from West Line of Section

LEASE OPERATOR American Energies Corporation SPOT LOCATION _____ W/2 W/2 SW _____
ADDRESS 155 N Market, Suite 710 Section 33 Township 20 Range 1W
CITY, STATE, ZIP Wichita, KS 67202 County McPherson
PHONE # 316-263-5785 Date Well Completed 6/29/04
Character of Well D & A Date Plugging Commenced 6/30/2004
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 6/30/2004
(date)

The plugging proposal was approved on 6/30/04
by Jack Luthi - State Plugging Agent (KCC District Agent's Name)
Is ACO-1 Filed? Attached If not, is well log attached? Attached
Producing Formation(s) None Depth to Top _____ Bottom _____ T.D. _____
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface	Water sands	292'	0'	8 5/8" 20#	292'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Ran 4 1/2" drill pipe to 3050', brake circulation, mix to pump 35 sx 60/40 poz with 4% gel and disp. Pulled 4 1/2" drill pipe up to 332', brake circulation mix to pump 65 sx 60/40 poz 4% gel and disp. Pulled 4 1/2" drill pipe up to 60'. Mix and pump 25 sx 60/40 poz 4% gel to surface. Ran 4 1/2" drill pipe in rat hole. Mix and pump 15 sx 60/40 poz 4% gel to surface and cement stayed in collar.

Name of Plugging Contractor United Cementing and Acid Co., Inc.
Licence No. 30437
Address 2510 West 6th City: Eldorado State: Kansas Zip 67042
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Energies Corporation (Operator)

STATE OF KANSAS COUNTY OF Sedgwick, ss.
Alan L. DeGood, President _____ (Employee of Operator or (Operator) of above described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of
the above described well as filed that the same are true and correct, so help me God.
(Signature) Alan L. DeGood
(Alan L. DeGood, President, American Energies Corporation)
(Address) 155 North Market, Suite 710 City: Wichita State: Kansas Zip 67202

SUBSCRIBED AND SWORN TO me this 7th day of July, 2004

Melinda S. Wooten
Melinda S. Wooten, Notary Public

My Commission Expires: 3/12/2008



Form CP-4
Revised 12-92

RECEIVED
JUL 23 2004
KCC WICHITA

Bu