

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-20778-00-00

LEASE NAME Kinney Chester Sand Umn

WELL NUMBER 201

2970 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 25 TWP. 34 RGE. 35 (E or W)

COUNTY Stevens

Date Well Completed 12-4-84

Plugging Commenced 6-17-04

Plugging Completed 6-18-04

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Oxy USA, Inc.

ADDRESS 701 N. Kansas PO Box 2528 Liberal, KS. 67905

PHONE (620) 629-4206 OPERATORS LICENSE NO. 5447

Character of Well oil

(Oil) Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-17-04 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Chester Depth to Top 6512 Bottom 6569 T.D. 6650

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1759	—
				5 1/2	6630	2330

JUL 27 2004

KCC WICHITA

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section.
Mixed 400 lb. hulls & 25 sx cmt. to plug perfs from 6512 to 6312. Shoot & pull 5 1/2 to 1800 Circ. hole w/mud & mixed 50 sx plug 1800 to 1650
30 sx 600 to 500 10 sx 40' to 0 Cut off & capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.

STATE OF Kansas COUNTY OF Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Kenny Andrews

(Address) PO Box 2528 Liberal, KS. 67905



AND SWORN TO before me this 26th day of July, 2004

Kath R Poulton
Notary Public

My Commission Expires: November 8, 2006