

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: MICA Energy Corp.

Address: P. O. Box 20707, Oklahoma City, OK 73156

Phone: (405) 942-4552 Operator License #: 32047

Type of Well: oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 5-21-04 2/19/04 KCC (Date)  
BEW 7-22-04

by: Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

Simpson Sd. Depth to Top: 4523' Bottom: 4530' T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 151-10054-00-00

Lease Name: FH Kerr FH KCC BEW

Well Number: 2 7-26-04

Spot Location (QQQQ): C - SW - SE - SW  
330 Feet from  North /  South Section Line

1650 Feet from  East /  West Section Line

Sec. 27 Twp. 29 S. R. 14  East  West

County: Pratt

Date Well Completed: 3-31-1945

Plugging Commenced: 5-20-04

Plugging Completed: 5-24-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	763'	none
				5 1/2"	4523'	1730'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set cast iron bridge plug @ 4500'. Pumped 2 sacks cement on bridge plug. Shot 5 1/2" casing off at 1730'. Pulled to 800'. Spotted 50 sacks cement at 800', 40 sacks cement at 400', 20 sacks cement from 0-40'.

Job complete 5-24-04.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 401 W. Main, Lyons, KS 67554

Name of Party Responsible for Plugging Fees: MICA Energy Corp.

State of Oklahoma County, Oklahoma, ss.

MICHAEL E. CARR (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 20707, Oklahoma City, OK 73156

SUBSCRIBED and SWORN TO before me this 20 day of July, 2004

Mary Alice Folk My Commission Expires: 12-15-04  
MARY ALICE Notary Public FOLK Commission # 00020363

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bm

*Per Operator 7-26-04*

RECEIVED  
JUL 26 2004  
KCC WICHITA



**MICA ENERGY CORP**

P.O. Box 20707 • Oklahoma City, Oklahoma 73156 • (405) 942-4552 • Fax (405) 942-6686

**Michael E. Carr**  
**President**

RECEIVED  
JUL 26 2004  
KCC WICHITA

July 20, 2004

Barbara Montgomery  
Production Department  
Kansas Corporation Commission  
Conservation Division, Finney State Office Bldg.  
130 S. Market, Room 2078  
Wichita, KS 67202-3802

Re: Well Plugging Reports (CP-4)  
F H Kerr 4 and F H Kerr 2  
Pratt County, KS

Dear Ms. Montgomery:

In accordance with your letters of July 15, 2004, enclosed are the two plugging reports that we are resubmitting on these wells.

Please call us if there is additional information needed.

Thank you for your assistance in this matter.

Sincerely,

Mary Alice Folk

# KANSAS

CORPORATION COMMISSION

KATHLEEN SEBELIUS, GOVERNOR  
BRIAN J. MOLINE, CHAIR  
JOHN WINE, COMMISSIONER  
ROBERT E. KREHBIEL, COMMISSIONER

July 15, 2004

MICA Energy Corp.  
PO Box 20707  
Oklahoma City, OK 73152

RE: Well Plugging Report  
API Well No. **15-151-10054-00-00**  
**27-29-14w**  
**F H Kerr 2**  
Pratt, County, Kansas

To Whom It May Concern:

On **July 8, 2004**, a well plugging record (CP-4) was received on the **F H Kerr #2** well. A file review shows that a lot of the information submitted on the CP-4 is incorrect. Please resubmit the CP-4 with the correct information. The footages or spot location are incorrect, and the well name is incorrect. If this information that we have is wrong please let me know. You can call me at (316) 337-6225.

Sincerely,

Barbara Montgomery  
Production Department

Enclosures