

2-12

41

4-071034

TO: STATE CORPORATION COMMISSION CONSERVATION DIVISION - PLUGGING 200 COLORADO DERBY BUILDING WICHITA, KANSAS 67202

RECEIVED STATE CORPORATION COMMISSION FEB 24 1993 CONSERVATION DIVISION Wichita, Kansas

API number: 15-153-20,795-00-00

SW SW NE /4 SEC. 06, 02 S, 34 W 2970 feet from S section line 2310 feet from E section line

Operator license# 6875

Lease Skolout well # 1

Operator: Marmik Oil Company

County Rawlins

Address: 200 N. Jefferson Suite 500 El Dorado, Arkansas 71730

Well total depth 4450 feet 144.62 Conductor Pipe: 0 inch @ 0 feet Surface pipe 8 5/8 Inch @ 287 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Abercrombie Drilling License# 5422 30684

Address: 801 Union Center - Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 12 Month: February Year: 93

Plugging proposal received from: Harold Maley

Company: Abercrombie Drilling, Inc. Phone: 316-262-1841

Were: 8 5/8" - 287' S.P. cwc. w/190 sx. 60/40 pozmix - 2% gel. - 3% c.c. by Allied Cement. K.C. Well - No ar buckle - Elev. 3175' - Anhy. 3028' - no circulation problems. Mud condition 54 vis. - 9.1 weight - 10.4 water loss. Proposal 190 sx. 60/40 pozmix - 6% gel. - 1 sack flocele. Heavy mud between all plugs. 25 sx. @ 3030' - 100 sx. @ 2270' w/1 sx. F.C. - 40 sx. @ 330' - 10 sx. 40'. 15 sx. in rathole (circulate)

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 2:00 P.M, Day: 12, Month: February, Year: 93

Actual plugging report: Ordered 190 sx. 60/40 pozmix - 6% gel. - 1 sx. flocele. Circulate hole. Spot and displace all cement through drill pipe with heavy mud between all plugs. 1st. plug @ 3030' w/25 sx. cement. 2nd. plug @ 2270' w/100 sx. cement with 1 sx. Flocele. 3rd. plug @ 330' w/40 sx. cement. 4th. plug @ 40' w/10 sx. cement. 15 sx. in Rathole.

Remarks: Cement by Allied Cement Company.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING X, CASING. Elevation: 3175 GE

I did not observe the plugging.

INVOICED

Signature of Marion J. Schmidt (agent)

DATE 3-1-93

INV. NO. 37424