

4-032279

8-21

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-153-20,788-00-01
130'W.
S2 S2 NW /4 SEC. 06, 02, 34 W
2970 feet from S section line
4090 feet from E section line

R.L. Hrbek
31274

Operator license# ~~31664~~
Operator: Northwest Well Service
Address: 17509 County Road - #14
Fort Morgan, CO 80701

Lease: Frank Trust Well # 1
County: Rawlins 144.63
Well total depth 4450 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 302 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Company Tools License# 31664

Address: 17509 County Road #14 - Fort Morgan, CO 80701

Company to plug at: Hour: P.M. Day: 21 Month: August Year: 1997

Plugging proposal received from: Randy

Company: Northwest Well Service Phone: -

Were: Order 175 sxs 60/40 pozmix - 10% gel - 300# hulls.
Allied Cement Company.
Order B.P. and common cement.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [], Part [X], None []

Completed: Hour: 4:15 P.M., Day: 21 Month: August, Year: 1997

Actual plugging report: 8 5/8" set at 302' w/150 sxs cwc. 4 1/2" set at 4446' with 590 sxs
Prod. Perfs at 4317' - 4320'. Shots at 2200' - 1500' - 1200' - 1000'. Recovered 1000' of
4 1/2" casing. Set B.P. at 4250' with 25 sxs common cement on plug. Squeezed 8 5/8" of with
175 sxs cement blend with 300# hulls. Mixed into Max. P.S.I. 200#. Held. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

JAN 15 1998
01-15-1998
CONSERVATION DIVISION
Wichita, Kansas

Remarks:
Condition of casing (in hole): GOOD BAD Anhy. plug: YES X NO
Bottom plug (in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did and not observe the plugging.

Carl Goodrow
(agent)

DATE 1-16-98
INV. NO. 49935

HD

8-21 JAN 29 1998