

11-1-87

To: 6 070613
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 023-20,251 -00-00
S/2 NE, SEC. 26, T 2 S, R 42 (W/E)

TECHNICIAN'S PLUGGING REPORT

3300 feet from S section line
1320 feet from E section line

Operator License # 5447

Lease Name Northrup Well # A #7

Operator: Cities Service Oil & Gas Corp
Name &
Address 3545 N.W. 58th Street

County Cheyenne 163.38

Oklahoma City, Ok 73112

Well Total Depth 5027 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 421

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor B. J. Titan License Number

Address Box 27 Oakley, Kansas

Company to plug at: Hour: 6:00PM Day: 1 Month: Nov. Year: 19 87

Plugging proposal received from Chuck Harsman

(company name) Cities Services Oil and Gas Co. (phone) 405-949-4268

were: 8 5/8" 421' S.P. cwc w/265 sks cement. Cemented by B. J. Titan.
Lansing and Marmington Well Elv. 3706', Anh 3598', mud condition 9.3 weight;

43 viscosity: 15. water loss. Proposal 260 sks 60/40 Pozmix 6% Gel 3% Ca Cl and
8 5/8" plug. Spot with drill stem, mud between all plugs. Circulate hole (Vis 42-45).

25 sks at 4800'; 25 sks at 4500'; 25 sks at 3620'; 100 sks at 2880'; 50 sks at 471';
10 sks at 40'; 15 sks in rat hole; 10 sks in mouse hole (circulate)
Plugging Proposal Received by Marion J. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:00AM Day: 1 Month: Nov. Year: 19 87

ACTUAL PLUGGING REPORT Ordered 260 sks 60/40 Pozmix 6% Gel 3% Ca Cl and 8 5/8" plug.

Spotted with drill stem, reconditioned hole, heavy mud between all plugs.

1st plug at 4800' w/25 sks cement; 2nd plug at 4500' w/25 sks cement; 3rd plug at
3620' w/25 sks cement; 4th plug at 2880' w/100 sks cement w/1 sk Celloflake; 5th plug
at 471' w/50 sks cement; 6th plug Hulls and plug at 40' w/10 sks cement; 15 sks in
rat hole. (circulate) 10 sks in mouse hole (circulate) Cemented by B. J. Titan.

Remarks:
(If additional description is necessary, use BACK of this form.) 11-30-87

INVOICED
Get observe this plugging.

Signed Marion J. Schmidt
(TECHNICIAN)
Marion J. Schmidt

DATE 12-4-87
INV. NO. 19090