

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24492-00-00

Spot: S2S2NWSW

Sec/Twnshp/Rge: 36-20S-12W

1480 feet from S Section Line, 4620 feet from E Section Line

Lease Name: DANNEBOHM

Well #: 1

County: BARTON

Total Vertical Depth: 3460 feet

Operator License No.: 4184

PROD Size: 4.5 feet: 3459 75 SX CMT

Op Name: CASINO PETROLEUM CO.

SURF Size: 8.625 feet: 268 175 SX CMT

Address: PO BOX 415

ELLINWOOD, KS 67526

Well Type: EOR

UIC Docket No: E26516.1

Date/Time to Plug: 04/26/2004 3:00 PM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTY ANDREW

Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-7397

Proposed
Plugging
Method:

Ordered 220 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: PAT STAAB

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 04/26/2004 5:00 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

Sanded bottom off to 3200' with 4 sxs cement using a dump bailer.
Cut casing at 2013' - pulled to 1384'.
Tied onto casing - pumped 70 sxs 60/40 pozmix with 200# hulls mixed in.
Pulled casing to 600' - pumped 80 sxs cement with 200# hulls mixed in.
Pulled casing to 300' - pumped 50 sxs 60/40 pozmix.
POOH. Pulled rest of casing - hole standing full of cement.

Perfs:

Top	Bot	Thru	Comments
3420	3421		
3414	3415		
3398	3400		
3323	3328		
3287	3289		

RECEIVED
MAY 03 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Patricia Staab

(TECHNICIAN)

INVOICED

DATE

45504

INV. NO.

2004061491

Form CP-2/3

APR 28 2004

STATE: KANSAS COUNTY: BARTON REISSUE 36-20S-12W
FIELD: CHASE-SILICA W2 SW
OPER: CASINO PET 1480 FSL 660 FWL SEC
WELL: 1 DANNEBOHM WELL CLASS: D ELEV: 1827 KB
API: 15-009-24492 STATUS: D&A-O 1818 GR
SPUD: 10/15/91 COMP: 12/05/91
DTD: 3459 LTD: FTD: ARBUCKLE PBTD:

LOC: 6 MI S/SW ELLINWOOD, KS

IP: COMP 12/5/91, D&A
NO CORES, THREE DSTS

LOG TOPS:

ANHYDRITE	590 1237	BROWN LIME	3142 -1315
HEEBNER	3008 -1181	LANSING-KANSAS CITY	3155 -1328
TORONTO	3024 -1197	ARBUCKLE	3395 -1568
DOUGLAS	3040 -1213		

TD 3459 -1632

LOG TYPES: CNDL, DI;

CSGS: 8 5/8 @ 268 W/175 SX, 4 1/2 @ 3459 W/75 SX; TBG: 2 3/8 @ 3270; RIG REL
10/20/91

DSTS: DST # 1, (MISRUN) PKR FAILED DST # 2 (ARBUCKLE) 3357-3403, OP 45 MIN, SI
55 MIN, OP 15 MIN, SI 15 MIN, REC: 30 FT SOCM, IFP 31, FFP 31, IFP 31,

(OVER)

COPYRIGHT 1992 PETROLEUM INFORMATION CORPORATION

DATE 10/23/92 CARD #00046-KS