

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-21135-00-00
Spot: W2NWNW Sec/Twnshp/Rge: 20-20S-5W
4580 feet from S Section Line, 4950 feet from E Section Line
Lease Name: BRIGGS Well #: 1-A
County: MCPHERSON Total Vertical Depth: 3452 feet

Operator License No.: 9971
Op Name: KODIAK PETROLEUM, INC.
Address: PO BOX 4677
ENGLEWOOD, CO 80155

PROD Size: 5.5 feet: 3451
SURF Size: 8.625 feet: 220

\$112¹⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/28/2004 12:00 PM
Plug Co. License No.: 7868 Plug Co. Name: KIZZAR WELL SERVICING, INC.
Proposal Rcvd. from: GENE GROUNDS Company: KODIAK PETROLEUM, INC. Phone: (580) 651-2116

Proposed Plugging Method: Sand to 3,325' & top with 5 sxs. cement. Shoot casing off. Pull casing to 825' & spot 35 sxs. cement. Pull casing to 430' & spot 35 sxs. cement. Pull casing to 270' & circulated cement to the surface.

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/29/2004 3:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 3,325' & topped with 5 sxs. cement. Shot casing off @ 1,208'. Pulled casing to 840' & spotted 35 sxs. cement w/100# hulls. Pulled casing to 444' & spotted 35 sxs. cement w/100# hulls. Pulled casing to 286' & circulated 95 sxs. cement to the surface.

Perfs:

Top	Bot	Thru	Comments
3374	3411	CSG	

**RECEIVED
KCC DISTRICT #2
JUL 21 2004
WICHITA, KS**

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 28 2004
CONSERVATION DIVISION
WICHITA KS

Remarks: USED 60/40 POSMIX W/4% GEL BY ALLIED CEMENTING COMPANY, INC. INVOICE #17282.

Plugged through: CSG

District: 02

Signed Michael Wilson
(TECHNICIAN)

INVOICED
DATE 7-29-04
INV NO 2005060234