

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23455-00-00
Spot: NENWNW Sec/Twnshp/Rge: 19-26S-3E
400 feet from N Section Line, 685 feet from W Section Line
Lease Name: PHANNENSTIEL Well #: 1
County: BUTLER Total Vertical Depth: 3320 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

CIBP Size: feet: 3250
PROD Size: 5.5 feet: 3317 50 SX CMT
SURF Size: 8.625 feet: 208 150 SX CMT

\$ 107⁹⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/22/2004 11:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. D/B/A BRADEN PETROLEUM & WELL PLUGGING
Proposal Rcvd. from: R. A. SCHREMMER Company: BEAR PETROLEUM, INC. Phone: (620) 438-2852

Proposed Plugging Method: Bottom plug -- Sand back to 3142'; dump bail; 5 sxs; shoot and pull pipe.
Top plug -- Run tubing to 258'; circ cement to surface.

RECEIVED
KCC DISTRICT #2
JUL 23 2004
WICHITA, KS

Plugging Proposal Received By: BILL JOHNSON WitnessType: NONE
Date/Time Plugging Completed: 07/22/2004 1:15 PM KCC Agent: BILL JOHNSON

Actual Plugging Report:

Bottom plug -- Sanded back to 3142' and dump bail 5 sacks of cement. Shot and pulled pipe.
Top plug -- Ran 1-1/2" poly pipe to 270' and circulated cement to surface.
140 sacks of 60/40 posmix with 4% gel.
Inspected site at 4:10 pm; cement to surface.

Perfs:

Top	Bot	Thru	Comments
3316	3316		3316 - 3316-1/2
3296	3297		
3192	3193		


RECEIVED
KANSAS CORPORATION COMMISSION
JUL 28 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: TOP PLUG -- COPELAND ACID #24940

Plugged through: TBG

District: 02

Signed


(TECHNICIAN)

INVOICED
DATE 7.29.04
INV. NO. 2005060232