

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-30262-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 36-24S-3E
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: MOORE-B Well #: N-1
County: BUTLER Total Vertical Depth: 2710 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH STREET
NEWTON, KS 67114

PROD Size: 4.5 feet: 2700 50 sxs
SURF Size: 7 feet: 123

#8808

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/13/2004 8:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: RICK SCHRIEBER Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method:

See actual report. Casing leaks from 1218' through 1500'.

**RECEIVED
KCC DISTRICT #2
JUL 23 2004**

WICHITA, KS

Plugging Proposal Received By: JEFF KLOCK WitnessType: NONE
Date/Time Plugging Completed: 07/14/2004 4:30 PM KCC Agent: JEFF KLOCK

Actual Plugging Report:

Perfs:

Sanded back bottom to 2650'. Set CIBP at 1000'. Spotted 2 sacks of cement on top of CIBP. Perforated 4-1/2" casing with 3 holes at 250'. Pumped cement down 4-1/2" casing and circulated to surface.

Good cement returns. Cement fell approximately 20' inside the 4-1/2" casing. Topped off cement on 7/15/2004.

60/40 posmix with 4% gel.

aka Moore B #6

**RECEIVED
KANSAS CORPORATION COMMISSION
JUL 28 2004
CONSERVATION DIVISION
WICHITA, KS**

Remarks: COPELAND CEMENT #24936

Plugged through: CSG

District: 02

Signed Jeff Klock
(TECHNICIAN)

INVOICED

DATE 7-29-04

INV. NO. 2002060236

e