

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21503-00-00
Spot: NWNESE Sec/Twnshp/Rge: 9-30S-7W
2310 feet from S Section Line, 990 feet from E Section Line
Lease Name: M C SIMON Well #: 1
County: KINGMAN Total Vertical Depth: 4196 feet

Operator License No.: 4706
Op Name: MESSENGER PETROLEUM, INC.
Address: 525 S. MAIN ST.
KINGMAN, KS 67068

PROD Size: 4.5 feet: 4196 150 SX CMT
SURF Size: 8.625 feet: 213 200 SX CMT

#136³⁷

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/01/2004 4:00 PM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Perfs 4106'-4118'
Plugging PBTD 4142'
Method: Sand to 4050' & 4 sxs; 1250' & 35 sxs; 750' & 35 sxs;
Circ cmt 260' - 0'

RECEIVED
KCC DISTRICT #2
JUN 24 2004
WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: NONE

Date/Time Plugging Completed: 06/01/2004 4:00 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perforations were covered with sand to 4050' and capped with 4 sacks of cement. The 4-1/2" casing recovered from 2800'. Pulled casing to 1250' and spotted 35 sacks of cement. Pulled casing to 750' and spotted 35 sacks of cement. Pulled casing to 260' and circulated 130 sacks of cement to surface.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
4106	4118		

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 27 2004

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENT

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

INVOICED

DATE 7-28-04

INV. NO. 2005060205