

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-20623-00-00  
Spot: NESW Sec/Twnshp/Rge: 6-30S-8W  
1980 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: WHITMER Well #: C-1  
County: KINGMAN Total Vertical Depth: 4261 feet

Operator License No.: 4706  
Op Name: MESSENGER PETROLEUM, INC.  
Address: 525 S. MAIN ST.  
KINGMAN, KS 67068

PROD Size: 4.5 feet: 4261 125 SX CMT  
SURF Size: 8.625 feet: 231 200 SX CMT

*\$138<sup>48</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/08/2004 11:15 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Perfs 4167'-4182'  
Plugging Sand to 4115' & 4 sxs; 1300' & 35 sxs; 850' & 35 sxs  
Method: Circ cmt 280' - 0'  
Rec 3200'

RECEIVED  
KCC DISTRICT #2  
JUN 24 2004  
WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/08/2004 11:15 PM KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

The perforations were covered with sand to 4080' and capped with 4 sacks of cement. Casing recovered from 3200'. Pulled casing to 1300' and spotted 35 sacks of cement. Pulled casing to 850' and spotted 35 sacks of cement. Pulled casing to 280' and circulated cement to surface.  
60/40 posmix with 4% gel.

**Perfs:**


Top	Bot	Thru	Comments
4167	4182		

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 27 2004  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENT #15519

Plugged through: CSG

District: 02

Signed   
(TECHNICIAN)

INVOICED  
DATE 7-28-04  
INV. NO. 2005060205