

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21347-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 17-16S-13W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: SCHAEFFER Well #: 1
County: BARTON Total Vertical Depth: 3470 feet

Operator License No.: 30380
Op Name: HUPFER OPERATING, INC.
Address: PO BOX 216
HAYS, KS 67601

PROD Size: 5.5 feet: 3455 w/75 sxs cmt
SURF Size: 8.625 feet: 256 w/100 sxs cmt

\$ 112⁹⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/18/2004 11:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: CRAIG OIL COMPANY Phone: (316) 265-4651

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/18/2004 3:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Sanded to 3350'.
Cut off at 1835'.
Pulled to 1675' - pumped 115 sxs 60/40 pozmix - 10% gel cement with 300# hulls.
Pulled to 975' - pumped 40 sxs cement with 100# hulls.
Pulled to 550' - pumped 30 sxs cement with 100# hulls.
Pulled to 200' - pumped 35 sxs cement.
POOH.
Topped off with 20 sxs cement.

RECEIVED
JUL 28 2004
KCC WICHITA

Remarks: COPELAND CEMENTING.

Plugged through: CSG

District: 04

170

Signed _____

Case Morris

(TECHNICIAN)

INVOICED

DATE

7-28-04

INV. NO.

2005060205

JUN 30 2004

CRUDE PRODUCERS, INC.
 P.O. BOX 55, RUSSELL, KS.

#1 SCHAEFFER

17-16-13W
 SW SW SE

CONTR REVLIN DRLG., INC. CTY BARTON

GEOL HAP PRYOR FIELD TRAPP

E 1962 KB CM 3/16/78 CARD ISSUED 12/14/78 P 25 BOPD
 ARB 3416-3418

+	+	+
+	+	+
+	+	+

API 15-009-21,347

SMP	TOPS	DEPTH	DATUM
ANH		928	+1034
B ANH		958	+1004
HEEB		3097	-1135
TOR		3116	-1154
DOUG SH		3129	-1167
BR LM		3175	-1213
LANS		3186	-1224
B KC		3404	-1442
ARB		3412	-1450
RTD		3470	-1508

8-5/8" 256/100 sx, 5 1/2" 3455/75 sx
 NO LOG
 DST (1) 3405-21/30-55-30-30, 1000' GIP,
 600' GSMO, SIP 905-795#, FP 65-144#
 185-216#
 MICT - CO, PF 8/3416-3418, AC 100 GAL,
 POP, P 25 BOPD

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS