

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-03954-00-00
Spot: SENWNE Sec/Twnshp/Rge: 26-18S-10W
4290 feet from S Section Line, 1700 feet from E Section Line
Lease Name: ROELFS TWIN Well #: 3
County: RICE Total Vertical Depth: 2683 feet

Operator License No.: 30535
Op Name: HARTMAN OIL CO., INC.
Address: 12950 E. 13TH
WICHITA, KS 67230

PROD Size: 7 feet: 2672
SURF Size: 10.75 feet: 264

\$ 87²⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/25/2004 8:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JIM MORTON Company: HARTMAN OIL CO., INC. Phone: (620) 791-7187

Proposed Plugging Method: Run tubing to 2,670' & spot 30 sxs. cement. Perforate 7" casing @ 1,250', 800', and 315'. Run tubing to 1,250' & spot 50 sxs. cement. Pull tubing to 800' & spot 50 sxs. cement. Pull tubing to 315' & circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/28/2004 11:30 AM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

06/25/04 - Ran 2 7/8" to 2,670' & spotted 30 sxs. cement. Pulled tubing. Perforated 7" casing @ 1,250', 800', & 315'. Ran tubing to 1,272' & spotted 50 sxs. cement - did not circulate. Tried to circulate w/240 bbls. water - would not circulate. Pulled tubing - static fluid level @ 340'. Ran tubing to 1,272' & spotted 100 sxs. cement - did not circulate. W.O.C. Ran tubing to 1,336' - no cement. Pulled tubing to 1,272' & spotted 100 sxs. cement - did not circulate. There was communication with Roelfs #2 well bore. 06/28/04 - Ran wireline & tagged cement @ 2,160'. Sat 7" C.I.B.P. @ 1,300'. Ran 2 7/8" tubing to 1,252' & spotted 50 sxs. cement - circulated fluid to surface. Pulled tubing to 795' & spotted 50 sxs. cement. Pulled tubing to 318' & circulated 170 sxs. cement to the surface.

Perfs:

Top	Bot	Thru	Comments
2672	2683	OH	

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 27 2004
CONSERVATION DIVISION
WICHITA, KS

RECEIVED
KCC DISTRICT #2
JUL 14 2004
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENTING. INVOICE #24509.

Plugged through: TBG

District: 02

Signed Michael Wilson
(TECHNICIAN)

INVOICED

DATE 7-28-04

INV. NO. 2005060204