

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20153-00-00
Spot: SWNW Sec/Twnshp/Rge: 25-8S-25W
3194 feet from S Section Line, 4726 feet from E Section Line
Lease Name: SCHAMBERGER Well #: 1
County: GRAHAM Total Vertical Depth: 3990 feet

Operator License No.: 33069
Op Name: ENCORE OPERATING COMPANY
Address: 1601 BLAKE STREET, SUITE 500
DENVER, CO 80202

PROD Size: 4.5 feet: 3989 150 SX CMT
SURF Size: 8.625 feet: 214 160 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/21/2004 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JAY JOHNSON Company: ENCORE OPERATING COMPANY Phone: (303) 595-9251

Proposed Plugging Method: Ordered 275 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/21/2004 12:15 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perforated 4 1/2" casing at 1300' and 2200'. PBSD 3950'.
Tied to 4 1/2" casing and squeezed 200 sxs cement with 500# hulls.
Max. P.S.I. 900#. S.I.P. 600#.
Tied to 4 1/2" x 8 5/8" annulus and squeezed 50 sxs cement.
Max. P.S.I. 200#. S.I.P. 150#.
Total of 250 sxs 60/40 pozmix - 10% gel and 500# hulls.

Perfs:

Top	Bot	Thru	Comments
3918	3923		

RECEIVED
JUL 28 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. RGN TANK-WATER.

Plugged through: CSG

District: 04

Signed Roger L. Moses
(TECHNICIAN)

NO.

INVOICE

DATE 7-28-04

INV. NO. 2005060214

JUL 23 2004

