

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-22060-00-00  
Spot: E2E2SE Sec/Twnshp/Rge: 24-18S-7W  
1320 feet from S Section Line, 330 feet from E Section Line  
Lease Name: CARLTON E Well #: 1  
County: RICE Total Vertical Depth: 3250 feet

Operator License No.: 6141  
Op Name: CORONADO OIL & GAS, INC.  
Address: PO BOX 1285  
GREAT BEND, KS 67530

PROD Size: 4.5 feet: 3223 125 SX  
SURF Size: 8.625 feet: 218 130 SX

*\$ 105<sup>63</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/07/2004 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: See actual report.

RECEIVED  
KCC DISTRICT #2  
JUL 15 2004  
WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE  
Date/Time Plugging Completed: 06/07/2004 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2940' and put 4 sacks of cement on top. Cut off 4-1/2" casing at 1800'. Pulled casing to 950' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 600' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 270' and circulated cement to surface.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3184	3186		
3178	3182		
2996	3000		
2992	2994		

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 27 2004  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED #17942

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED  
DATE 7.28.04  
INV. NO. 2005060203