

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21182-00-00
Spot: SENENE Sec/Twnshp/Rge: 6-21S-6W
4208 feet from S Section Line, 329 feet from E Section Line
Lease Name: WOLF B Well #: 2-6
County: RICE Total Vertical Depth: 3548 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

PROD Size: 5.5 feet: 3547 150 SX CMT
SURF Size: 8.625 feet: 213 200 SX CMT

\$115³¹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/17/2004 9:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Sand to 3,425' & top with 5 sxs. cement. Shoot casing off. Pull casing to 1,050' & spot 35 sxs. cement. Pull casing to 625' & spot 35 sxs. cement. Pull casing to 265' & circulate cement to the surface.

RECEIVED
KCC DISTRICT #2

JUL 8 - 2004

Plugging Proposal Received By: MICHAEL WILSON

Witness Type: PARTIAL

Date/Time Plugging Completed: 06/17/2004 3:00 PM

KCC Agent: MICHAEL WILSON

WICHITA, KS

Actual Plugging Report:

Sanded to 3,420' & topped with 5 sxs. cement. Ripped casing at 1,900'. Pulled casing to 1,056' & spotted 35 sxs. cement w/100# hulls. Pulled casing to 633' & spotted 35 sxs. cement w/200# hulls. Pulled casing to 296' & circulated 100 sxs. cement to the surface.

Perfs:

Top	Bot	Thru	Comments
3490	3500		
3476	3482		

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 27 2004

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENT. INVOICE # 24479.

Plugged through: CSG

District: 02

Signed

Michael Wilson

(TECHNICIAN)

INVOICED

DATE

7-28-04

INV. NO.

2005060202