

#04-2-2398

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20509-00-00
Spot: SESESE Sec/Twnshp/Rge: 30-15S-8W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: ALDEN Well #: 2
County: ELLSWORTH Total Vertical Depth: 2672 feet

Operator License No.: 5047
Op Name: RUPE OIL COMPANY, INC.
Address: PO BOX 783010 111 WHITTIER #1000
WICHITA, KS 67278

PROD Size: 4.5 feet: 2668 175 SX
SURF Size: 8.625 feet: 237 150 SX

86⁸⁴

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/02/2004 10:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-7397

Proposed Sand off perf @ 2590' and put 4 sxs cement on top. Cut off 4-1/2" casing. Pull casing to 900' and pump 35 sxs; pull casing to 600' and pump 35 sxs; and pull casing to 290' and circulate cement to surface.
Plugging Method:

RECEIVED
KCC DISTRICT #2
JUL 15 2004

Plugging Proposal Received By: VIRGIL CLOTHIER

WitnessType: PARTIAL

WICHITA, KS

Date/Time Plugging Completed: 07/02/2004 12:00 PM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded off perforations to 2550' and put 4 sacks of cement on top. Cut off casing at 1618'. Pulled to 900' and pumped 35 sacks of cement with 100 lbs cotton hulls. Pulled to 600' and pumped 35 sacks of cement with 100 lbs cotton hulls. Pulled casing to 290' and circulated cement to surface.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
2648	2660		
2318	2324		
2224	2228		

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 27 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND CEMENT #23548

Plugged through: CSG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

INVOICED

DATE 7-28-04
TRK. NO. 2005060207